

MRBIR Executive Meeting February 11, 2016

Army Corps of Engineers Bureau of Reclamation





PROJECT STATUS

- FONSI April 2015
- Awarded construction contract August 2015
- Preliminary Injunction granted September 2015
- Stipulated Stay Agreement signed January 2016
- Moving Forward
 - EIS
 - ESA Consultation

Purpose and Need

Improve Pallid Sturgeon Passage


 Continue Viable and Effective Operation of the Lower Yellowstone Irrigation Project

Alternatives

- No Action
- Rock Ramp
- Bypass Channel
- High Flow Channel
- Pumping
- Non-Weir Alternative

Intake Diversion Dam Fish Passage Project EIS Rock Ramp

- Construct concrete weir
- Shallow sloped boulder and cobble rock ramp
- Weir crest would vary in elevation, including a low flow notch



Intake Diversion Dam Fish Passage Project EIS Bypass Channel


Construct concrete weir

• Construct side channel to carry 15% of main channel

flow

 Grade control and bank stabilization in side channel

 Fill part of existing high flow channel



Intake Diversion Dam Fish Passage Project EIS High Flow Channel

Excavate existing high flow channel to meet BRT


criteria


 Maintain existing weir



Pumping

- Remove existing dam
- Screened surface water intakes or infiltration galleries constructed along the Yellowstone River
- Existing headworks may be used depending on water levels
- Power supply and backup generators
- Pipelines





Non-Weir

Remove existing dam

• Infiltration galleries constructed along the Yellowstone River

Conservation measures

Alternative energy sources



Schedule

- Public Scoping: January 4 February 18, 2016
- Public Review of DEIS: May 25 July 11, 2016*
- Final EIS: No later than December 31, 2016*
- Record of Decision: No sooner than 30 days following issuance of the Final EIS

^{*} Dates subject to change

2016 Field Activities

 Entrainment monitoring at Intake headworks

Passage monitoring